

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For HCRS use only  
received **JAN 12 1983**  
date entered

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections

**1. Name**

historic Oakley

and/or common N/A

**2. Location** E of upperville on

street & number U.S. 50 N/A not for publication

city, town Upperville vicinity  vicinity of ~~congressional district~~

state Virginia code 51 county Fauquier code 061

**3. Classification**

<b>Category</b>	<b>Ownership</b>	<b>Status</b>	<b>Present Use</b>	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<u>N/A</u>	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

**4. Owner of Property**

name Mrs. Archibald Cary Randolph

street & number Oakley

city, town Upperville N/A vicinity of state Virginia 22176

**5. Location of Legal Description**

courthouse, registry of deeds, etc. Fauquier County Courthouse

street & number N/A

city, town Warrenton state Virginia

**6. Representation in Existing Surveys**

title Virginia Historic Landmarks Commission  
Survey 30-46 has this property been determined eligible?  yes  no

date 1982  federal  state  county  local

depository for survey records Virginia Historic Landmarks Commission, 221 Governor Street

city, town Richmond state Virginia 23219

## 7. Description

<b>Condition</b>		<b>Check one</b>	<b>Check one</b>
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		N/A

### Describe the present and original (if known) physical appearance

#### SUMMARY DESCRIPTION

Oakley stands on a gradual rise of land overlooking the fields and grazing pastures of northern Virginia's finest hunt country. The pastoral setting is especially beautiful. The house is a well-preserved example of the Italianate style prevalent in America during the 1850s. Its articulated openings, low-pitch overhanging roof with brackets, long porches, and pronounced details such as its semi-hexagonal bays, quoins, decorative sawn-work, and spiral stair distinguish the house as one of the most notable examples of the style in the region.

#### ARCHITECTURAL ANALYSIS

Completed in 1857 Oakley is a brick residence stuccoed and scored to resemble stone. The three-bay, T-shaped building rises 2½ stories above an English basement. A bracketed cornice outlines the standing-seam metal roof pierced by tall decorative-paneled chimneys. The roof also has a glazed cupola to provide light for the interior stairwell.

Anthemions decorate the gable ends of the building's main block and the central projecting pavilion. This motif is repeated directly below in the shouldered surround of the second-story center window. The flanking second-story windows have similar surrounds that step up into semi-rounded heads with no anthemions. Plain, shouldered surrounds encase the first-floor windows. Throughout the main block the windows are casements divided by cross-shaped mullions. The rear ell and additions are lit by a variety of casement and hung-sash windows.

The central two-story pavilion dominates the facade (north). The pavilion contains the entrance with paneled double doors and sidelights surmounted by a broad elliptical arch. Sheltering the entrance is a porch which was at one time a single bay but now extends the length of the facade. Chamfered posts support a modillion block frieze and decorative sawn-cut balustrades on the first and second stories. The corners of the front (north) and side (east and west) elevations are articulated by corbeled brick imitating rusticated quoins.

The most dramatic feature of Oakley is the two-level porch which wraps around the rear (south) ell. Originally rising the full two stories without interruption, the porch was altered in 1975 by the addition of a second floor with a decorative sawn-cut railing. The alteration was very carefully carried out in the spirit of the original fabric. The attenuated chamfered posts with brackets forming capitals exhibit stylistic similarities to the tall, slender columns at nearby Welbourne, Loudoun County, also originally a Dulany family property. Welbourne, listed on the Virginia Landmarks Register and the National Register of Historic Places, was enlarged during the mid-19th century when its present porch was added. Although not identified, the same builder is thought to have been employed at the two houses.

Semi-hexagonal bays embellish the east and west elevations. These projections were each built as a single story, but the west bay was enlarged in 1960. Pilasters separate the recessed round-arched window openings on each side. One- and two-story rear additions to the east and south elevations were constructed during the early to mid-20th century.

(See Continuation Sheet #1)

## 8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/ humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		

**Specific dates** 1857 **Builder/Architect** Unknown

### Statement of Significance (in one paragraph)

#### STATEMENT OF SIGNIFICANCE

Oakley, which sits grandly amid the rolling hills of northern Virginia's scenic countryside, is a sophisticated and well-preserved example of an Italianate country house. While generally popular in mid-19th-century America, Italianate houses are comparatively rare in rural Virginia which saw little building immediately before the Civil War. The picturesque romanticism expressed by the house is symbolic of the life style of its builder, Richard Henry Dulany, a country gentleman. Dulany was founder of the Upperville Colt and Horse Show, the oldest horse show in the country and now the highlight of equestrian life in the Commonwealth's most prestigious hunt country.

#### HISTORICAL BACKGROUND

In 1853 Richard Henry Dulany, prominent citizen and horseman of Loudoun County, purchased 878 acres of land just east of Upperville in Fauquier County from G.W. Carlyle Whitney. Since the wife of the grantor in this transaction was a Dulany, it can be assumed this property had been in the Dulany family for some time. Shortly after his purchase, Richard H. Dulany built the present house called Oakley for his son, Henry Grafton Dulany. Completed in 1857, the house clearly was the seat of a family of substance; its taxed value was listed as \$6,000. Because of stylistic similarities between Oakley and Richard Dulany's Loudoun County mansion, Welbourne (NRHP 1971), which was greatly enlarged ca. 1857, it would appear that Dulany engaged the same craftsmen for both places. Title to Oakley was not transferred to the younger Dulany until 1862.

Richard Henry Dulany is best known as the founder of the Upperville Colt and Horse Show. The show grounds, located nearby, were the site of the first recorded horse show in America in June of 1852. Perhaps mindful of the historic importance of the occasion, Dulany had traveled to New York and engaged Mr. Tiffany himself to design the silver cup for the winner. Dulany's show was reorganized in 1869 and has continued ever since as a highlight of the equestrian and social life of the Loudoun-Fauquier area. Oakley and its surrounding fields have traditionally been the site of hunts and horse shows. Apparently Mr. Dulany's interest in thoroughbreds began when he found a near-frozen horse and saved its life. He worked for much of his life thereafter to improve the care and breeding of fine horses.

At the time the house was built, the villa-type house had become a popular form in American domestic architecture especially for country houses. A.J. Downing in his The Architecture of Country Houses (New York, 1850) notes the following on villas:

## 9. Major Bibliographical References (See Continuation Sheet #2)

Downing, A.J. The Architecture of Country Houses. New York, 1850 .  
 Fauquier County Deed Books 54, 59. Land Tax Books 1854-1870.  
 Loudoun-Fauquier Magazine, Summer 1931.  
 Scheel, Eugene M. The Guide To Fauquier. Warrenton: Warrenton Printing and Publishing Co., 1976.

## 10. Geographical Data

Acreeage of nominated property 221 acres

Quadrangle name Rectortown, VA

Quadrangle scale 1:24000

### UMT References

A 

1,8	2,5,2	0,2,0	4,3	1,9	2,0,0
Zone	Easting		Northing		

B 

1,8	2,5,2	2,4,0	4,3	1,8	0,0,0
Zone	Easting		Northing		

C 

1,8	2,5,2	2,6,0	4,3	1,7	3,2,0
Zone	Easting		Northing		

D 

1,8	2,5,2	0,1,0	4,3	1,7	0,6,0
Zone	Easting		Northing		

E 

1,8	2,5,1	3,6,0	4,3	1,7	4,6,0
Zone	Easting		Northing		

F 

1,8	2,5,1	4,7,0	4,3	1,8	4,0,0
Zone	Easting		Northing		

G 

1,8	2,5,1	9,2,0	4,3	1,9	2,2,0
Zone	Easting		Northing		

H 

Zone	Easting		Northing		

**Verbal boundary description and justification** The boundaries for Oakley conform to those which currently comprise the Oakley Farm tract and which are recorded in the Fauquier County Deed Book. For the main part of the tract, the western boundary is a straight line extending 3000 feet through open fields. The southern boundary extends for 2500 feet along a straight line (See Continuation Sheet #2)

### List all states and counties for properties overlapping state or county boundaries

state N/A code  county N/A code

state N/A code  county N/A code

## 11. Form Prepared By

name/title Virginia Historic Landmarks Commission Staff

organization Virginia Historic Landmarks Commission

date June 1982

street & number 221 Governor Street

telephone (804) 786-3144

city or town Richmond

state Virginia 23219

## 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national  state  local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature

*H. Bryan Mitchell*

H. Bryan Mitchell, Executive Director

title Virginia Historic Landmarks Commission

date JUN 15 1982

For HCRS use only

I hereby certify that this property is included in the National Register

*Tommy Lee Doyel*  
Keeper of the National Register

date 2/24/82

Attest: *Patrick Andrews*  
Chief of Registration

date 2/15/93

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

OAKLEY, FAUQUIER COUNTY, VA

Continuation sheet #1

Item number 7, 8

Page 1, 1

7. DESCRIPTION -- Architectural Analysis

The interior room arrangement consists of a central hall providing access to the three major first-floor rooms. The focal point of the hall is a graceful stair which spirals to the third floor. It features a heavy squared newel with carving on each face topped by a finial, carved tread brackets, and a paneled spandrel. The black-and-white tile floor is a recent addition. Each of the first-floor rooms including the hall has heavy molded baseboards, broad flat architrave trim with a rounded backband, and vertical panel doors with applied moldings.

Sliding paneled double doors separate the hall from the parlors to the east and west. The fireplaces in the two rooms are set into projecting chimney breasts and finished with black marble mantels comprised of simple pilasters and a plain frieze. Each parlor opens into the semi-hexagonal-ended bay, the east bay finished with its original panels and applied molding below the windows. Located behind the hall is the dining room. The marble mantel in this room has a round-arched opening, paneled spandrels, and centered cartouche. Narrow, floor-to-ceiling windows flank the mantel.

The second-floor rooms used for bedrooms are simpler versions of the first-floor rooms. The original water system was removed in 1950 when the attic story was finished for living accommodations. Rainwater collected in a lead-lined tank on this level was piped to various rooms of the house.

The original smokehouse and an early building, possibly a tenant house that now serves as guest quarters, stand at the rear of the building. The well-landscaped yard is bordered by a rubblestone wall on the west and wood rail fence on the east separating the lawn from the fields and pastures. The house is approached by a long, straight avenue leading from Route 50. Located on the property are a variety of modern barns and tenant houses.

MPM

8. SIGNIFICANCE -- Historical Background

More strictly speaking, what we mean by a villa, in the United States, is the country house of a person of competence or wealth sufficient to build and maintain it with some taste and elegance...The villa, or country house proper, then, is the most refined home in America --the home of its most leisurely and educated class of citizens.<sup>1</sup>

Dulany fit Downing's image of a person of competence and wealth and the picturesque style of Oakley became symbolic of such a life style.

A lively diary kept by Ida Dulany, young wife of Henry Grafton Dulany, indicates that Oakley housed Confederate troops during the Civil War. Mrs. Dulany notes that she watched several cavalry skirmishes from the balcony of her room at Oakley and that the house was also occupied by Union officers. A 1931 interview with Rozier Dulany, grandson of Richard Henry Dulany, revealed that Oakley had one of the earliest water systems in

(See Continuation Sheet #2)

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

OAKLEY, FAUQUIER COUNTY, VA

Continuation sheet #2

Item number 8

Page 2

8. SIGNIFICANCE -- Historical Background

Fauquier County. The system consisted of a lead-lined tank in the attic which was filled with rainwater and then piped to various parts of the house.

Oakley stands in the beautiful hunt country of Fauquier County as both a reminder of late-antebellum plantation grandeur and a symbol of the fine horsemanship indigenous to the northern Virginia area. Today Oakley is owned by Mrs. Archibald Cary Randolph who has encouraged and continued Oakley's use as a setting for famous Virginia hunts and horse shows.

MTP/MPM

<sup>1</sup>A.J. Downing, The Architecture of Country Houses (New York, 1850), pp. 257-8.

9. BIBLIOGRAPHICAL REFERENCES

Washington, D.C. US Department of the Interior. National Park Service. National Register of Historic Places Inventory. Nomination Report, Welbourne, Loudoun County, Virginia, 1971.

Years of Anguish - Fauquier County, Virginia, 1861-1865. Compiled for the Fauquier County Civil War Centennial Committee, 1965.

10. GEOGRAPHICAL DATA -- Verbal Boundary Description and Justification (continued)

line, paralleling a landing strip on the adjacent farm. The eastern boundary extends from the southeastern corner along a straight line for 1000 feet then easterly for 300 feet, then northerly for 1500 feet, then in a curve to the west for approximately 500 feet, then northerly along a straight line for approximately 1400 feet. The northern boundary of the main tract follows a fence line for approximately 2300 feet east to west. The tract also includes a narrow strip of land along either side of the approach road extending from the main tract approximately 3000 feet to the farm entrance to U.S. Route 50. The strip is approximately 300 feet wide. (Fauquier County Tax Map 8, Parcels 15 and 27A)

Boundary Justification: The entire tract of approximately 221 acres has been included in the Oakley nomination in order to provide a protected entrance and an appropriately rural setting for the house. The house stands in an elevated position in the center of the tract with completely unobstructed views across the surrounding open fields to the adjacent farms and mountains in the distance. The house remains the center of an important equestrian operation and thus requires sufficient land attached to it to maintain its integrity as a rural landmark. The strip of land including the approach road from U.S. Route 50 has been included in order to maintain the view and approach to the house from the main entrance to the farm. The house is plainly evident down the approach road and forms a striking vista termination. No other buildings other than the historic outbuildings in the main house yard have been noted as being of significance to the nomination. The numerous buildings noted on the topographic map scattered through the farm are all modern farm buildings or tenant houses. Most of the boundaries of the property are defined by fence lines stretching across open pasture.

United States Department of the Interior  
National Park Service

88 603282

Substantive Review

Oakley  
Fauquier County  
VIRGINIA

Working No. 1/12/83-99  
Fed. Reg. Date: 2.7.84  
Date Due: 2/10/83 - 2/26/83  
Action:  ACCEPT 2/24/83  
 RETURN  
 REJECT  
Federal Agency: \_\_\_\_\_

- resubmission
- nomination by person or local government
- owner objection
- appeal

Substantive Review:  sample  request  appeal  NR decision

Reviewer's comments:

*Architecturally significant building historically associated with VA. Thoroughbred horse society*

Recom./Criteria accept A&C  
Reviewer Patrick Andrews  
Discipline Historian  
Date 2/15/83  
 see continuation sheet

Nomination returned for:  technical corrections cited below  
 substantive reasons discussed below

1. Name

2. Location

3. Classification

Category	Ownership	Status	Present Use
	Public Acquisition	Accessible	

4. Owner of Property

5. Location of Legal Description

6. Representation in Existing Surveys

has this property been determined eligible?  yes  no

7. Description

Condition	Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed	<input type="checkbox"/> moved date _____

Describe the present and original (if known) physical appearance

- summary paragraph
- completeness
- clarity
- alterations/integrity
- dates
- boundary selection

## 8. Significance

Period \_\_\_\_\_ Areas of Significance—Check and justify below

Specific dates \_\_\_\_\_ Builder/Architect \_\_\_\_\_

Statement of Significance (in one paragraph)

- \_\_\_\_\_ summary paragraph
- \_\_\_\_\_ completeness
- \_\_\_\_\_ clarity
- \_\_\_\_\_ applicable criteria
- \_\_\_\_\_ justification of areas checked
- \_\_\_\_\_ relating significance to the resource
- \_\_\_\_\_ context
- \_\_\_\_\_ relationship of integrity to significance
- \_\_\_\_\_ justification of exception
- \_\_\_\_\_ other

---

## 9. Major Bibliographical References

---

## 10. Geographical Data

Acres of nominated property \_\_\_\_\_

Quadrangle name \_\_\_\_\_

UMT References \_\_\_\_\_

Verbal boundary description and justification \_\_\_\_\_

---

## 11. Form Prepared By

---

## 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

\_\_\_\_\_ national \_\_\_\_\_ state \_\_\_\_\_ local

State Historic Preservation Officer signature \_\_\_\_\_

title \_\_\_\_\_ date \_\_\_\_\_

---

## 13. Other

- \_\_\_\_\_ Maps
- \_\_\_\_\_ Photographs
- \_\_\_\_\_ Other

Questions concerning this nomination may be directed to \_\_\_\_\_

Signed \_\_\_\_\_ Date \_\_\_\_\_ Phone: 202 272 - 3504

Comments for any item may be continued on an attached sheet



OAKLEY

Fauquier County, VA

Credit: VA Historic Landmarks Commission

Date: 1979

Neg. Filed: VA State Library, Richmond, VA

View from North

1 of 1

Neg. No. 4867

File No. 30-46



View from Northwest



View from Southwest



First-Floor South Room (Dining Room)  
First-Floor East Parlor




Center Hall, View toward South




USGS 7.5' quadrangle (scale:1:24000)  
Rectortown, Va. 1970  
OAKLEY, Fauquier Co., Va.  
UTM References:  
A-18/252020/4319200 B-18/252240/4318000  
C-18/252260/4317320 D-18/252010/4317060  
E-18/251360/4317460 F-18/251470/4318400  
G-18/251920/4319220

Mapped, edited, and published by the Geological Survey  
Control by USGS and USC&GS  
Topography by photogrammetric methods from aerial photographs  
taken 1965 and 1969. Field checked 1970  
Supersedes Army Map Service map dated 1943  
Polyconic projection. 1927 North American datum  
10,000-foot grid based on Virginia coordinate system, north zone  
1000-meter Universal Transverse Mercator grid ticks,  
zone 18, shown in blue  
Fine red dashed lines indicate selected fence and field lines where  
generally visible on aerial photographs. This information is unchecked

UTM GRID AND 1970 MAGNETIC NORTH  
DECLINATION AT CENTER OF SHEET



ROAD CLASSIFICATION  
Primary highway, all weather, hard surface  
Secondary highway, all weather, hard surface  
Light duty road, all weather, improved surface  
Unimproved road, fair or dry weather  
U. S. Route  
State Route



THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS  
FOR SALE BY U. S. GEOLOGICAL SURVEY, WASHINGTON, D. C. 20242  
AND VIRGINIA DIVISION OF MINERAL RESOURCES, CHARLOTTESVILLE, VIRGINIA 22903  
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

RECTORTOWN, VA.  
N 3852.5—W 7745/7.5

1970  
AMS 5461 IV NE—SERIES V834

MRS. A. C. RANDOLPH  
OAKLEY FARM  
UPPERVILLE, VIRGINIA 22176

May 24, 1982

Corrine P. Hudgins,  
Registrar for H. Bryan Mitchell  
State Historic Preservation Officer  
221 Governor Street  
Richmond, Virginia 23219

Dear Miss Hudgins:

RE: OAKLEY, Fauquier County

In answer to your letter of May 14th, I would be most interested in having Oakley registered in the Virginia Landmarks Register and the National Register of Historic Places.

As you know, this area has a great deal of history about it, and I think it would be proper that the place which I now call SALEM (formerly called EASTERN VIEW) on the corner of Route 50 and 719 should also be considered for these Registers.

Please let me know if there is anything further I can do.

Sincerely yours,



Mrs. A. C. Randolph.

TAR/r

MEMBERS

MRS. KENNETH R. HIGGINS, CHAIRMAN  
MRS. NELLIE WHITE BUNDY, VICE CHAIRMAN  
DAVID A. HARRISON, III  
DONALD HAYNES  
W. BROWN MORTON, III  
FREDERICK D. NICHOLS  
RICHARD M. B. RENNOLODS  
FRED W. WALKER  
MRS. T. EUGENE WORRELL



COMMONWEALTH of VIRGINIA  
*Virginia Historic Landmarks Commission*

W. JAMES MITCHELL  
EXECUTIVE DIRECTOR

221 GOVERNOR STREET  
RICHMOND, VIRGINIA 23219  
TELEPHONE: (804) 786-3143

January 7, 1983

Mr. Jerry Rogers, Keeper  
National Register of Historic Places  
Department of the Interior  
National Park Service  
440 G Street, NW  
Washington, DC 20243

RE: NATIONAL REGISTER OF HISTORIC PLACES NOMINATION REPORTS

Dear Mr. Rogers:

The four enclosed reports are being submitted in nomination to the National Register of Historic Places:

1. Middlebrook Historic District, Augusta County (comment from county)
- ✓ 2. Oakley, Fauquier County (comment from owner)
3. Planters National Bank, Richmond (city)
4. Woodford, Richmond County

The fourth, Woodford, is a resubmission, having had the Verbal Boundary Description clarified as your staff requested.

Sincerely yours,

*Corrine P. Hudgins (swa)*

Corrine P. Hudgins  
Registrar

Enclosures

CPH/vmm

